

REP: 2021/GSA/T0023

Date: November 15, 2021

TENDER NOTICE

INVITATION TO BID FOR CONSTRUCTION OF 170 SINGLE FLOODS PROTECTED AND GENDER SEGREGATED LATRINES FOR NORMAL PEOPLE AT IDP'S CAMPS AND HOST COMMUNITIES WITH HAND WASHING FACILITIES IN JOWHAR DISTRICT, HIRSHABELLE STATE, UNDER SHF PROJECT

GSA is a local humanitarian, non-governmental organization that relieves the suffering of those affected by war, natural disaster and disease in Somalia, by providing life-saving assistance. GSA work with communities in urban and rural areas, isolated villages, IDP's camps and disaster sites by provide access to safe drinking water and improve the sanitation and hygiene of community members, technical education and assist in promoting peace and good governance among the affected communities.

GSA, with funding from Somalia Humanitarian Fund (SHF) invites tender bids for Construction of 170 single floods protected and gender segregated latrines for normal people at IDP's camps and host communities with hand washing Facilities

Requested Materials:

Construct 170 single flood protected latrines for normal people and will be constructed complete with hand washing facility for safe disposal of excreta to prevent AWD and other feacal oral diseases. Designs of the latrines will consider flood, disable persons, ensure safety of children, privacy, disable people, dignity and protection of women and girls (lockable doors, solar light during night, separate latrines for men and women and marked based on gender), and possibility of desludging. To prevent effects of flooding the floor will be raised 0.5m above

the ground level. Market-based programming (MBP) modality will be used in all the construction activities to strengthen the existing markets by procure local materials based on competitive among local suppliers in project target areas. See the attached BOQ and designs.

The bidders should meet following requirements:

1. Bank account statement last six months
2. Must have relevant borehole rehabilitation experience.
3. Valid municipality license from the Regional State
4. Updated company profile with the full information of work
5. Similar work experience conduct., amount in USD, location and by which organization.
6. Duly completed bill of quantity with company stamp
7. Proposed work schedule (workplan)

The deadline for tender submission is COB 09th December 2021

Interested bidders will submit all their documents to GSA Office In Jowhar, HirShabelle State. Contact: 252 1 **612350** or 252 0 **615943720**

GSA reserves the right to reject any bids and to cancel the procurement process wholly or in part without assigning and or giving reason(s) for its decisions. GSA not bound to accept the lowest. The decision of the tender committee will be final.

The BOQ Attached with this notice

**BILL OF QUANTITIES FOR CONSTRUCTION OF SINGLE FLOOD PROTECTED LATRINES
IN JOWHAR, HIRSHABELLE SATE, SOMALIA**

| Item | Item Description | Unit | Qty | Rate | Amount(USD) |
|-------------------------------|---|------|------|------|-------------|
| 1 | Excavation works | | | | |
| 1.1 | Clear site of all loose soil 300mm deep and dispose off as directed n.e 100m | M2 | 4 | | |
| 1.2 | Excavate 1.6m Long X 1.5m Wide pit from ground level upto 1m deep. | M3 | 2.4 | | |
| 1.3 | Ditto but, 2.0m Long X 1m Wide upto 2m deep. | M3 | 4 | | |
| 1.4 | Excavate foundation tranches of 6.2m long, 0.5m wide, 0.3m deep | M3 | 0.93 | | |
| Total Excavation works | | | | | |
| 2 | Foundation works | | | | |
| 2.1 | Construct rubble stone retaining wall insite the excavated pit, 400mm wide upto 1000mm deep, use mortar at the ratio of 1:4 | M3 | 2.48 | | |
| 2.2 | Provide materials and lay rubble in foundation wall 400 mm wide x 500 mm height in cement sand mortar ratio 1:4 | M3 | 2.46 | | |
| 2.3 | Cast 200mm thick plain concrete around the latrine, and construct concrete steps, use concrete ratio of 1:3:6, | M3 | 1.52 | | |
| 2.4 | Supply and fix hardwood 75mm-100mm diam. treated with wood preservative in superstructure - wall framework (2.7m high spaced at 1200mm lengthwise, and circumferential railing at 750mm c/c. Rate to include for cutting and nailing all members for circumferential railing and door frames | LM | 16.7 | | |
| 2.5 | Supply and install 100mm PVC vent pipe 3000mm to detail complete with vent covers. | Pcs | 2 | | |
| 2.6 | Supply and fix 150mm dia PVC pipe 1500mm as drain pipe for squathole to latrine pit as specified in design drawing. Ensure slope 1:1.5 for self cleaning. Rate to include for construction of foot rest to engineer specifications | Pcs | 2 | | |
| 2.7 | Supply and fill hardcore park to foundation for latrine compacting in 150mm layers n.e Latrine excavated material to be used | M3 | 1.6 | | |
| 2.8 | Supply materials and construct well vibrated mass concrete ratio 1:2:4 to slab for latrine base and pit cover all uniform. Provide for squatholes with foot rest to design detail | M3 | 1.8 | | |
| 2.9 | Reinforcement | | | | |
| 2.9.1 | Provide and place Y10 steel bars @ 250mm c/c to latrine pit slab | Kgs | 11 | | |

| | | | | | |
|--|---|------|-------|--|--|
| 2.9.2 | Supply and lay BRC A142 to latrine substructure slab | SM | 4 | | |
| 2.9.3 | Soffits to slab, 150mm x 25mm | LM | 11 | | |
| Total Foundation works | | | | | |
| 3 | Superstructure wall cover | | | | |
| 3.1 | Supply and fix Superstructure walling- G30 galsheet corrugated iron sheets to superstructure wall and privacy wall height as specified using roofing nails | M2 | 19.14 | | |
| 3.2 | Provide for 50mmx12mm lipping to all iron sheet joints sharp edges for safety to users. Rate to include for painting colour matching to sheets | LM | 10 | | |
| Total Superstructure wall cover | | | | | |
| 4 | Roofing | | | | |
| 4.1 | Provide for 75x50mm hardwood truses and fix to roof | LM | 6.2 | | |
| 4.2 | Supply and fix 50mmx50mm roof purlins | LM | 6.2 | | |
| 4.3 | Supply and fix galsheet corrugated translucent roofing sheet. | SM | 2.4 | | |
| 4.4 | Provide for 1" hoop iron as support to trusses and purlin well nailed to wall passes | Kgs | 2 | | |
| 4.5 | Supply and fix 200mmx25mm wrot fasciaboard to roof | LM | 8 | | |
| Total Roofing | | | | | |
| 5 | Finishing works | | | | |
| 5.1 | Supply materials and plaster 25mm cement mortar mix 1:3 and 25mm thick in rubble walling and all concreted surfaces. Provide for smooth trowel finish to screed | M3 | 1 | | |
| 5.2 | Provide materials, fabricate and fix door 1.8m x 0.9m made of galvanized iron sheet on timber frame. Provide for 50mmx12mm lipping round the sheet edges painted to match. (The door opens Inside) | No. | 1 | | |
| 5.3 | Supply, cut and place coffee tray above door with 2"x1" lipping as frame | SM | 1 | | |
| 5.4 | Supply and fix Latches (8" external and 6" internal chrome coated bolts) - | No. | 2 | | |
| 5.7 | Provide materials and cast 600x600mm manhole cover 100mm thick. Use 8mm rebar | No. | 1 | | |
| 5.8 | Installation of solar lamp with accessories | Sets | 1 | | |
| 5.9 | Supply 20l white Jerrican, fitted with 1/2" tap on fabricated 700mm high steel stand. Use 25mmx25mmx3mm SHS for stand with 25mmx3mm flat bar around tank with provision for locking as support around jerrican. Provide for 2 logos on jerrican, spray painted to detail. | Sets | 1 | | |
| Total Finishing works | | | | | |
| GRAND SUMMARY | | | | | |
| | Excavation works | | | | |
| | Foundation works | | | | |

| | | | | | |
|--------------------------------------|---------------------------|--|--|------------|--|
| | Superstructure wall cover | | | | |
| | Roofing | | | | |
| | Finishing works | | | | |
| Sub-total for One (1) Latrine | | | | 1 | |
| Total cost for 170 latrine | | | | 170 | |

| Target Areas to be constructed Latrines | | |
|--|-----------------------|---|
| S/N | Village Name | Number of latrines for each IDP camp / Village |
| 1 | Geeda Barkan Village | 25 |
| 2 | Gafay Village | 20 |
| 3 | Lamo Wab Village | 20 |
| 4 | Sabuun Village | 20 |
| 5 | Tawakal IDPs camp | 15 |
| 6 | Jilyale IDP | 15 |
| 7 | Shaikh Omar IDPs camp | 15 |
| 8 | Biaso IDPs Camp | 18 |
| 9 | Waqwaqley IDPs Camp | 20 |
| Total | | 168 |

Company Name: _____

Contact Name: _____

Date : _____

Signature : _____